



BRAITHWAITE & CO LIMITED
(A Government of India Undertaking)

HEAD OFF. & REGD. OFF. : 5, HIDE ROAD, CALCUTTA – 43,
TEL 2439-7415, 2439-7413

FAX : 2439 7632 / 2439 5607 E-MAIL : braithwaite_co@yahoo.com

Ref: Tender Enquiry No. BWT/CORP/PUR/SP-236/NPG/2009

Dt. 25..02.2009

Dear Sirs,

Please quote your most competitive prices for the following repair work at our Angus Works.

Item No.	Description	Quantity
1.	Dismantling of existing Railway Track, Preparation of bed by excavating 3 – 0m wide X 0.6m depth X 500m long pit, filling by burnt sand, slag & debris, leveling by Power Roller for laying of Sleeper & 60 Kg/m Flat bottom Rail.	500 mts.
2.	Laying / Placing of Mono-block pre-cast Cement concrete Sleeper on leveled bed at the rate of 800mm apart from one another.	450 Nos
3.	a) Laying & fixing of new 60Kg/mt for Broad Gauge Railway Track including leveling, alignment & gauging. b) Mis-alignment of existing Rail are to lifted to match with the existing line in different locations accordingly.	500m 100m
4.	Existing Point crossings are to be serviced properly. During Servicing if any wooden Sleeper found damaged , the damaged wooden sleepers are to be placed by the contractor.	5 Nos
5.	3'-0" wide pathway on both sides of Railway Track & places between two rails required for movement of Fork-Lift & Shunter as follows : a) Proper Dressing, leveling & Ramming out side of Sleeper. b) Out side Edging & soling of No. 1 Picked Bricks. c) 100mm thick P.C.C.(M-15 Mixture) on the Brick soling. 7 days water spreading over concrete must be continued.	Along the Railway Track .1x1.0x 1000 =100cu.m

(TECHNICAL SPECIFICATIONS FOR RENOVATION OF RAILWAY TRACK (LABOUR CONTRACT ONLY) IS MENTIONED IN ANNEXURE-I.

a) Your quotation should reach us by 12.03.2009

b) Your quotation shall comprise of two parts :

- (i) Part- I : Techno-commercial Bid - Annexure -I
- (ii) Part – II : Price Bid – Annexure-II

Contd....2

Both the parts shall be submitted separately in two envelopes and these shall be put in a 3rd envelope and all the 3 envelopes shall be superscribed with our Tender Enquiry No. Tender Enquiry No. BWT/CORP/PUR/SP-236/NPG/2009 Dt. 25.02.2009 and due on

The quotation will be considered as cancelled if the documents required for Part-I & Part-II are not placed in the respective envelope.

c) Quotation must be sent in sealed cover either by registered post or may be dropped in our tender box no. 2 in case of hand delivery.

d) Sealed quotations addressed to Sr. Manager (Purchase), Braithwaite & Co. Ltd., 5 Hide Road, Kolkata 700043 may be dropped in our tender box no. 2 (in case of hand delivery) or may be sent by registered post, but must reach us positively within 12.03.09 .The techno-commercial part may be opened on .03.2009. You may be present during opening of the tender.

For Braithwaite & Co. Ltd

Note : Rs. 100/- by way of DD/Pay Order in favour of Braithwaite & Co. Ltd – Kolkata should be given alongwith your offer towards the cost of tender documents.

Ref: Tender Enquiry No. BWT/CORP/PUR/SP-236/NPG/2009

TECHNICAL SPECIFICATIONS FOR RENOVATION OF RAILWAY TRACK (LABOUR CONTRACT ONLY)

- 1.0 Description : It is to be required to revamp the existing Railway lines of Braithwaite Angus Works.
- 2.0 Scope of work : The scope of work as follows – Dismantling of existing Railway line, preparation of bed for laying of P.C.C/Wooden sleepers. Laying of 60 Kg/mt. flat bottom B.G. Rail maintaining proper leveling, gauging, Servicing of Point crossing, P.C.C. of 3'-0" Pathway on both sides & place between two rails etc. at the time of execution, all excavation job i.e. P.C.C. cutting, re-filling & re-correcting, cutting of bushes, Jungle & earth excavation for leveling the Track is totally contractor's responsibility.
- 3.0 **Material** : Braithwaite will supply 60 Kg/mt flat bottom Rail. Monoblock Pre-stressed Cement Concrete Sleeper, Elastic Rail Clip, Metal Liner, Rubber Pad, Square Head Bolts & Nuts, Dog Spikes, Std. Fish Plates and Std. Sal Wood sleeper. **All other materials, Civil materials & components required for total completion of the job is contractor's responsibility.**
- 4.0 Loading, unloading and carrying : Braithwaite shall provide only Space, Electric Power, & water. Shifting of damaged sleepers and Rail, Stacking at AW Steel yard is stock & Stores to working site) of new sleepers, Rail & other fixing components during execution of job shall be party's responsibility. Burnt sand to be collected from our Foundry Shop by the contractor. Cranes, if absolutely needed shall be provided by Braithwaite depending on availability and discretion of the Shop in charge. Crane operator should be arranged by the contractor.
- 5.0 Machineries, Tools & Labourers : All plants and machineries, handling equipment, Tools & Tackles, accessories experienced Supervisors & other related labourers required to execute the total job successfully shall be party's responsibility.
- 6.0 Workmanship & Quality of Work : The job to be carried out as per IRS specification and direction of Engineer in charge. The contractor should clear and leveled the floor after execution of the job. Regarding workmanship, the contractor should abide the decision of engineer in charge.
- 7.0 All safety rules & regulations to be followed by the party.
- 8.0 Prior to submission of offers, bidder may visit the site for study the scope of work and contact to Maintenance & Capital Project department for clarification if any. The quantity of items may vary $\pm 20\%$.
- 9.0 Payment shall be made on actual measurement basis. The bidder shall quote unit rate against item specified in annexure.

For Braithwaite & Co. Ltd.,

PART-I :Techno-commercial Part : General Terms & Conditions:

EMD : Rs. 5,000/- (Rupees Five thousand only) EMD is required to be deposited as Bid Security and to be submitted in the form of DD/Pay Order /Bank Guarantee in favour of Braithwaite & Co. Ltd payable at Kolkata. However, for SSI Units with single point registration with NSIC, payment of EMD can be considered for exemption to the extent of monetary limited granted on submission of valid NSIC registration certificate. Copy of the valid NSIC Registration Certificate should be furnished.

Security Deposit : @ 10% of the order value only in the form of DD/Pay/ Order/Bank Guarantee from an Indian Nationalised Bank to be submitted by the successful bidder within 10 days from the date of receipt of purchase order.

Performance Guarantee : After completion of the job, 10% of the total order value in the form of DD/Pay Order/Bank Guarantee to be submitted duly valid till completion of guarantee/warranty period. However, security deposit may be converted to Performance Bank Guarantee.

Payment Terms : a) 90% of the R/A bill submitted duly certified by Maint – In-charge and balance 10% of bill shall be released after completion of job.

Validity : Offer should remain valid for a period of 90 days from the date of opening of techno-commercial offer.

Quoted rate should remain firm till completion of the job and price variation shall not be entertained.

Price should be quoted both in figures and words and your quotation must be free from any kind of overwriting, alteration and correction.

BWT shall reserve the right to increase or decrease the ordered quantity at the same rate and terms.

BWT shall reserve the right to split up the tendered quantity.

BWT shall reserve the right to accept or reject the tender partly or fully without assigning any reason.

Liquidated Damages : In the event of failure to complete the job within the stipulated date, BWT reserves the right to recover a sum of 0.5% for every week or part thereof by way of LD subject to maximum limit of 10% of the ordered value.

Risk Purchase : In the event of your failure to complete the job, BWT reserves the right to procure the items mentioned in our purchase order from alternative sources on Risk Purchase Basis and recover the extra cost thereof, if incurred, from you.

Arbitration : Any dispute or difference whatsoever, arising between the parties and the purchaser out of relating to the construction, meaning, scope, operation or effect of the contract or validity or the breach thereof shall be settled by arbitration in accordance with the Rules of Arbitration in pursuance thereof shall be binding on the contractor.

Guarantee : The job shall be guaranteed for a period of 6 months from the date of hand over the machine.

Delivery/Completion period : Within 4 months from the date of receipt of Purchase Order.

For rail track job, the contractor must be a bonafied track laying contractor for the railways or others reputed companies. He has to submit all relevant documents including P.O. etc from railways or others reputed companies compulsorily in the techno-commercial bid otherwise the price bid will not be opened at all.

The contractor's rate should include supply of labour, tools & tackles, civil materials & components required for total completion of the job is contractor's responsibility.

Necessary sleepers (Monoblock pre-stressed cement Concrete & Wooden) & fixing accessories i.e. Dog Spikes, Rail Clips, Rubber Pad F.B. Rails and burnt foundry sand will be supplied by BWT free of cost. No charges will be paid for collection of materials from our stock/store to the site of work.

Contractor's rate should include cutting, making holes etc on old/new rails with all his equipments.

Quantity is approximate and may vary. Payment will be made on the basis of actual quantity done.

Contractor will fulfill all statutory obligation.

The contractor will maintain necessary registers as prescribed by the various acts in respect of his employee at his cost. Contractor will also comply with all others labour laws, rules & regulations and directives in force or framed/issued from time to time by Govt. (Central/State) or any local or duly constitution authority applicable to the work for which, no extra charge will be paid by us.

Contractor will ensure that persons employed by him on the works are competent in their respective occupations and the workmanship shall be of highest standard and to our satisfaction. It will be contractor's responsibility to adhere to safety regulations in force at the site of works and fulfill all statutory obligations applicable to that area and Braithwaite under no circumstances shall be held responsible to any mishap/accident/injury to contractor's workmen caused due to their negligence on safety measure.

Contractor will on the instruction of our Maint. (In-charge) –AW or his authorized representative, remove from our works any person/persons employed by the contractor who may be, in the opinion of our Maint (In-charge)- AW of his authorized representative, incompetent or misbehaving himself/themselves and such person/persons shall not be employed by the contractor further without the written permission of our Maint. (In-charge – AW).

Contractor will provide, at his cost a full time competent supervisor at the work site. The contractor shall receive instructions from our Maint. (In-charge) - AW or his authorized representative from time to time and shall be responsible to him for execution of work under his guidance.

Contd.....P/3

Joint Inspection of the job & scope of job as described is compulsory & price bid would not be opened.

Submission / payment of your bills : Payment will be made against contractor's running bills enclosing two copies of joint measurement sheet certifying the successful completion of work. Measurement sheets should be signed on behalf of Braithwaite by Maint (In-charge) – AW or his duly authorized representative.

Joint Inspection Report format

Declaration: - I/We have been inspected the site and studied the scope of job as offered by BWT. All the parameters of job was explained to me / us by BWT authority during joint inspection. I/We are submitting the quotation being fully aware of parameters of the job.

Special observation by the party if any.

Signature of BWT authority

Signature of party

Date:

Date:

PART – II: PRICE BID

- 1) The rate will remain firm till completion of supply.
- 2) The rate to be quoted both in figures and words.
- 3) Overwriting in price figure of the quotation will be rejected.
- 4) The bidder shall submit rate in the following format.

Item No.	Description	Quantity	Unit Rate (Rs.)	Total Amount (Rs.)
1.	Dismantling of existing Railway Track, Preparation of bed by excavating 3 – 0 wide X 0.6m depth X 500m long pit, filling by burnt sand, slag & debris, leveling by Power Roller for laying of Sleeper & 60 Kg/m Flat bottom Rail.	500 mts.		
2.	Laying / Placing of Mono-block pre-cast Cement concrete Sleeper on leveled bed at the rate of 800mm apart from one another.	450 Nos		
3.	A)Laying & fixing of new 52Kg/mt for Broad Gauge Railway Track including leveling, alignment & gauging. B) Mis-alignment of existing Rail are to lifted to match with the existing line in different locations accordingly.	500m 100m		
4.	Existing Point crossings are to be serviced properly. During Servicing if any wooden Sleeper found damaged , the damaged wooden sleepers are to be placed by the contractor.	5 Nos		
5.	3'-0" wide pathway on both sides of Railway Track & places between two rails required for movement of Fork-Lift & Shunter as follows : a) Proper Dressing, leveling & Ramming out side of Sleeper. b) Out side Edging & soling of 1No. Picked Bricks. c)100mm thick P.C.C.(M-15 Mixture) on the Brick soling. 7 days water spreading over concrete must be continued.	Along the Railway Track 1000 sq.m. 1000 RM 100 cub.m.		