



**BRAITHWAITE & CO LIMITED**

(A Government of India Undertaking)

**SUBSIDIARY OF BBUNL**

Accredited with Quality Standards

9001 for Cranes / ISO 9002 for Railway Wagons

HEAD OFF. & REGD. OFF. : 5, HIDE ROAD, CALCUTTA – 43, TEL 2439-7415, 2439-4114, 2439-6613,  
2439-7413 E MAIL : FAX : 91 (033)2439 7632 / 2439 5607

Ref: Tender Enquiry No. BWT/CORP/PUR/ERP/NPG- 2006

Dt. 15.11.2006

Dear Sirs,

Please quote your prices for shifting of Accounts Department, Purchase Department, PPC & Capital Project Department and enhancement of ERP Room for connectivity at BCL – Angus Works and enhancement of Computer Room, Clean Power for Head Office (CW) (on turnkey basis) including supply of file cabinet, wooden rack, computer chairs etc.. **The detailed Scope of Work is mentioned in Annexures (enclosed).**

**Note : Before submission of offer, Bidder must visit the sites, study the drawing where applicable and asses the actual volume of work.**

Your quotation shall comprise of two parts :

- a) Part- I : Techno-commercial Bid**
- b) Part – II : Price Bid**

Both the parts shall be submitted separately in two envelopes and these shall be put in a 3<sup>rd</sup> envelope and all the 3 envelopes shall be superscribed with our Tender Enquiry No. BWT/CORP/PUR/SP-272/NPG- 2006 Dt. 15.11.2006 and due on 30.11.2006.

The quotation will be considered as cancelled if the documents required for Part-I & Part-II are not placed in the respective envelope.

Quotation must be sent in sealed cover either by registered post or may be dropped in our tender box no. 2 in case of hand delivery.

Sealed quotations addressed to Manager (Purchase), Braithwaite & Co. Ltd., 5 Hide Road, Kolkata 700043 may be dropped in our tender box no. 2 (in case of hand delivery) or may be sent by registered post, but must reach us positively within 30.11. 2006.

An unconditional acceptance of commercial terms and conditions stipulated in Annexure-II of this tender enquiry is to be given alongwith the offer.

For Braithwaite & Co. Ltd.,

N. P. Ghosh  
Assistant Manager (Purchase)

Encl : Annexure-I & Annexure-II

**Scope of Work****(A) ACCOUNTS DEPARTMENT: Strong Room & Cash Room Only**

<b>SL. NO.</b>	<b>Description</b>	<b>Quantity</b>
<b>1.</b>	Dismantling, Re-sizing, Fitting & rigidly Fixing of 1no. 3'-6" x 6'-6" & 1 no. 3'-0" x 7'-2" size (Total: 44.25 sq.ft.) Steel Grill Door (Existing grill gate will be dismantle from A/cs deptt.)	<b>2nos.</b>
<b>2.</b>	Dismantling, Fitting & Fixing of existing steel collapsible gate size: 4'-0" x 6'-6" (Total 26 sq.ft.) & shutter (Existing collapsible gate in place of D-6 Position by dismantling the same from existing A/cs room.	<b>2nos.</b>
<b>3.</b>	Dismantling, Re-sizing, Fitting & Rigidly fixing of grill 2'-8" x 13'-0" adjacent to the door D5 (Sec B-B) & 7'-0" x 7'-10" & 3'-6" x 4'-0" Steel Grill – Door Portion D4 (Sec A-A. = 73.75 sq.ft.) as per drawing.	<b>2nos.</b>
<b>4.</b>	0'-5" (125mm) thk. Brickwork with cement Mortar (1:4) over floor & 12mm Cement Plaster (Cement sand mortar 1:6) with 10" neat cement finish on both sides of the wall including cost of material & labour. (~ 7.00 sq.m)  a) 4'-6" height x 13'-0" lg. ~ 60sq.ft. b) 3'-0" height x 5'-4" lg. ~ 16sq.ft.	<b>7m<sup>2</sup></b>
<b>5.</b>	0'-10" (250mm) thk. Brickwork with cement Mortar (1:4) over floor & 19mm & 12mm Cement Plaster (Cement sand mortar-1:4) with 10" neat cement finish on both sides of the wall including cost of material & labour.  a) 10'-0" height x 6'-10" lg. ~ 70sq.ft. - Vault room side. b) 10'-0" height x 13'-0" lg. ~ 130sq.ft. - Cash room side. c) 10'-0" height x 7'-10" lg. ~ 80sq.ft. - Corridor side. d) 0'-10" height x 13'-0" lg. ~ 11sq.ft. - Ceiling coverage. 3'-0" height x 21'-0" lg. ~ 63sq.ft. " "	<b>8.5m<sup>3</sup></b>
<b>6.</b>	Transprtation/shifting of vault /Iron safe from A/c dept. (2 <sup>nd</sup> Floor) to Gm's building 1 <sup>st</sup> Floor.	<b>L.S.</b>
<b>7.</b>	Plaster Repairing (side wall & ceiling), White/colour wa-sh (3coats) & painting (1 coat primer & 2 coats finish) of Iron beams, grills, grill gate, collapsible gate, rolling (shutters, wooden Frame, doors & windows after scrapping & cleaning etc.	<b>30 m<sup>2</sup> 200 m<sup>2</sup> 47 m<sup>2</sup></b>

**(B) PURCHASE DEPARTMENT:**

<b>SL. NO.</b>	<b>Description</b>	<b>Quantity</b>
<b>1.</b>	Supply & rigidly Fixing of 38mm thick 3'-6"x6'-6" Do or with 3"x3" size Sal Wood frame & panel with 1.5" thick Sal Wood frame covering both sides by 3mm thick Commercial ply wood (Best quality) with painting. (as per Drg.). Each door to be fitted with 1 No. Hyd. Door closure, 1 No. Mortise Lock (Godrej make) & other required accessories including cost of material & labour.	<b>1no.</b>
<b>2.</b>	Supply & Fixing of wooden board partition with 3"x3" Sal Frame, Covering by 1/8" thick Ply wood board (best quality) on both sides.  a) 3'-1" wide x 13'-0" lg. (Sec A-A) = 40 sq. ft. - M (Pur) Room. b) 3'-1" wide x 3'-5" lg. (Sec CC) = 10.5, Computer Room. c) 3'-1" wide x 12'-0" lg (sec CC) = 46 sq. ft. Computer Room. Including supply of 3"x3" Sal Wood Frame, Ply Wood, Labour Charge & etc to complete the work.	
<b>3.</b>	Fitting & fixing of 5mm thick clear glass in various sizes, Glass. (13 Nos.) will be fixed on paneling on Sal Wood frame by fixing in 3"x1.5" panel frame with aluminium section including supply of all materials & Al. Frame etc. to complete the job.  a) 4'-0"x12'-6" - 50 sq. ft. - Front of M (Pur) b) 4'-0"x3'-0" - 12 sq. ft. - Front of Computer Room c) 4'-2"x12'-3"x2 - 102 sq. ft. - Partition	
<b>4.</b>	Construction of 5" thick brick work (Cement mortar 4:1) over floor level, Cement plaster with 10" neat cement finish including supply of all materials & labours.  a) 3'-0"x12'-6" lg (Sec A-A) = 37.5 sq. ft. - Front of M (Pur) b) 3'-0"x12'-3" lg x 2 (Sec BB & CC) = 73.5 sq. ft. partition c) 3'-0"x3'-0" lg (Sec AA) = 9 sq. ft.	<b>3.42m<sup>2</sup></b>
<b>5.</b>	Construction of 10" thick brick wall (Cement mortar 4:1) over floor level Cement plaster with 10" neat cement finish including supply of all materials & labours.  a) 10"x10"x11'-10" = 8.2 Cu. ft. (Gap over ISMB)	<b>0.2m<sup>3</sup></b>
<b>6.</b>	Plaster Repairing (side wall & ceiling), White/colour wash (3 coats) & painting of Iron beams, grills, grill gate, collapsible gate, rolling shutters, wooden frame, doors & windows (1 coat Primer & 2 coats finish) after proper sc-raping & cleaning etc.	<b>10 m<sup>2</sup> 300 m<sup>2</sup> 47 m<sup>2</sup></b>

**(C) P.P.C. & CAPITAL PROJECT DEPARTMENT:**

<b>SL. NO.</b>	<b>Description</b>	<b>Quantity</b>
<b>1.</b>	Supply & rigidly of 3'-6"x6'-11".Size(2 Nos.)Door with 3"x3" size Sal Wood frame & panel (38mm thick) with 1.5"thk Sal Wood frame covering both sides by 3 mm thk.Commercial Ply wood (Best Quality)with painting(as per Drg.).Each door to be fitted with 1no.Hyd. Door Closure,1no. Mortise Lock(Godrej Lock)& other required accessories to complete the job including supply of materials & labour.	<b>2nos.</b>
<b>2.</b>	Supply & Fixing of wooden board partition with 3"x3" Sal Frame, covering by 1/8"thk.Ply wood board(Best Quality)on both sides. b)3'-1" wide x 32'-6" lg(Sec A-A)=100sq.ft. Including supply of 3"x3" Sal wood Frame,Ply wood, Labour charge & etc. to complete the work.	<b>100Ft<sup>2</sup></b>
<b>3.</b>	Construction of 5" thk brick work(Cement mortar 4:1) over floor level, both side cement plaster with 10" neat cement finish including supply of all materials & labour. 3'-0"x37'-4"(32'-6"- 7'-0"+11'-10")=112.0sq.ft.	<b>7.1 m<sup>2</sup></b>
<b>4.</b>	Fitting & Fixing of 5mm thick 'Clear Glass-17nos.'in various sizes. Glass to be fixed on paneling on Sal Wood frame 3"x3"& 3"x1.5" thk.Panel Frame with Aluminium section/frame including supply of all materials & Fasteners etc. to complete the job.(92.3sq.ft.)	<b>92 Ft<sup>2</sup></b>
<b>5.</b>	Plaster Repairing (side wall & ceiling),white/colour wash(3 coats) & painting(1 coat primer & 2 coats finish) of Iron beams,grills,grill gate,collapsible gate,rolling shutters,wooden Frame,doors & windows after proper scrapping & cleaning etc.	<b>20 m<sup>2</sup></b> <b>200 m<sup>2</sup></b> <b>30 m<sup>2</sup></b>
<b>6.</b>	Construction of 5"thk brick work(Cement mortar 4:1) over floor level,both side cement plaster with 10" neat cement finish including supply of all materials & labours d)3'-0"x50'-0"=150sq.ft. e)11'-0"x14'-0"=154sq.ft.	<b>154 Ft<sup>2</sup></b>
<b>7.</b>	1 no. Revolving Chair with castor wheel(make:Godrej)	<b>1no.</b>

**(D) ENHANCEMENT OF COMPUTER ROOM FOR CONNECTIVITY CONSTRUCTION  
OF ONE NO. URINAL AT ANGUS WORKS(SIZE OF URINAL- 4'-6"X5'0"X8'-0"HIGH):**

<b>SL. NO.</b>	<b>Description</b>	<b>Quantity</b>
1.	10" Brickwork(6:1)excluding opening for door.	112 Ft <sup>2</sup>
2.	4" RCC(1:2:4)Roof Casting 7'x 7'-6"	53 Ft <sup>2</sup>
3.	¼"thick Cement plaster(7:1)inside the wall & Ceiling.	150 Ft <sup>2</sup>
4.	½"thick Cement plaster(4:1)outside the wall.	200 Ft <sup>2</sup>
5.	3'x6'6" Sintex Door shutter & door frame.	1no.
6.	4'x3' wooden window fitted with glass pans	1no.
7.	Godrej Morice Lock for Door	1no.
8.	Fittings & Fixtures for door & window	L.S.
9.	Glaze Tile(4"x4")upto 6' high	100 Ft <sup>2</sup>
10.	Ceramic Urinal pot flat wall type(Parryware/Hindware)	1no.
11.	Wash basin 18"x12"(Parryware/Hindware)	1no.
12.	Necessary fittings and tap for urinal & basin	L.S.
13.	Wall fitted Looking Glass 2'x1'6"	1no.
14.	Soap stand, Towel Rod etc.	L.S.
15.	Towel(Big & Small)- 3 + 3 pcs.	6nos.
16.	½"galvenised Tata B-type pipe with required fittings	20m
17.	4" PVC Pipe for draining out with fittings & fixtures	20m

**(E)FURNITURE AND FITTINGS OF EXISTING ROOM:**

<b>SL. NO.</b>	<b>Description</b>	<b>Quantity</b>
1.	Revolving Sr.Executive Chair(Godrej make)	1no.
2.	Front Chair(Godrej Make)	6nos.
3.	Velvet and ¼" thick clear glass for existing Table	5nos.
4.	Polishing of Existing Table	60 m <sup>2</sup>
5.	Painting of existing Room & Toilet	50 m <sup>2</sup>
6.	Electrical fittings for Room & Toilet	L.S.

**(F) ENHANCEMENT OF COMPUTER ROOM CLEAN POWER FOR HEAD OFFICE,  
CLIVE WORKS & VICTORIA WORKS DUE TO CONNECTIVITY WITH ANGUS  
WORKS.**

SL. NO.	Description	Quantity	
1.	Supply & fitting of False Ceiling with all fittings.	426 Ft <sup>2</sup>	} Please see the drawing (ERP/1) attached.
2.	Wooden door to new position and shifting of one existing door.	3nos.	
3.	Construction & fitting of wooden partition wall with fitting of two Air Conditioner.	315 Ft <sup>2</sup>	
4.	Enhancement Networking Infrastructure	1set (100 Ft)	
5.	Supply of Steel File cabinet(3 racks)-18"x27"x42"with Locking arrangement-Make Godrej/Steelux/Raj & Raj	2nos.	
6.	Supply of Wooden rack with sunmica top(3 racks)-3'x1'-6"x3' high with locking arrangement	2nos.	
7.	Supply of wooden rack with sunmica top(3 racks)-4'x2'x3' high with locking arrangement.	2nos.	
8.	Supply of sunmica table top(12'x4')to set on existing Table	1no.	
9.	Supply of sunmica table top(8'x4')to set on existing Table.	1no.	
10.	Supply of White table cloth for conference table(Table Size 12'x4')	2nos.	
11.	Supply of white table cloth for conference table(table Size 8'x4')	2nos.	
12.	Supply of computer chair fitted with custor wheel, Make Godrej/steelux	8nos.	
13.	Supply of computer table 5'x2'-6" including one Board with 5 point electrical connection.	2nos.	
14.	Supply of computer table 4'x2' including one Board With 5 point electrical connection.	6nos.	
15.	Supply & fitting of Hydraulic door closer & Godrej Make Mortice Lock in existing door.	1 set	
16.	Supply of Front Grill for existing Air Conditioning Machines	4nos.	
17.	Supply of Brass name plate embossed with name of Departments (ERP,CPL &EDP)	3nos.	
18.	Supply and fitting of Calling bells with all accessories	3nos.	
19.	Supply of Curtains(Synthetic material)complete with All fittings and steel pipe.	1 set	
20.	Supply of wire less Audio system with 2 nos. button Microphone	1 set	
21.	Repairing of floor tiles (synthetic)with replacement of New tiles		
22.	Repairing/replacement of existing wall panel(laminated board)	100 Ft <sup>2</sup>	
23.	Re fixing of switch boards including new wiring where applicable	L.S.	
24.	Refixing,Repairing/Replacement of existing Tube lights, sheds and fans	10 sets	
25.	Repairing of existing wall Almirah shutters to bring in Workable condition	L.S.	
26.	Repairing of existing Tables,table locks and chairs With replacement covers	25nos.	
27.	Painting/Polishing of walls and wooden/ply panels	70m <sup>2</sup> 50 m <sup>2</sup> 30 m <sup>2</sup>	
28.	Computer covers(Good Quality)	100nos.	

**PART-I : TECHNO-COMMERCIAL BID****GENERAL TERMS & CONDITIONS:**

TENDER ENQUIRY NO. BWT/CORP/PUR/ERP/NPG- 2006 Dt. 11.11.2006

- 1) EMD : 2,000/- (Rupees Two Thousand only): EMD is required to be deposited as Bid Security and to be submitted in the form of DD/Pay Order in favour of Braithwaite & Co. Ltd payable at Kolkata. However, for SSI Units single point registration with NSIC, payment of EMD/Security Deposit can be considered for exemption to the extent of monetary limit granted on submission of valid NSIC registration certificate. Copy of the valid NSIC registration certificate should be furnished.
- 2) Credentials: Tenderer must submit the following documents as part of techno-commercial bid:
  - a) Copy of Sales Tax Clearance Certificate
  - b) Copies of Purchase Orders for similar type of job done .
- 3) Security Deposit : @ 10% of the order value only in the form of DD/Pay/ Order/Bank Guarantee from an Indian Nationalised Bank to be submitted by the successful bidder within 10 days from the date of receipt of purchase order.
- 4) Performance Guarantee : After completion of the job. 10% of order value in the form of Bank Guarantee from an Indian Nationalised Bank to be submitted duly valid till completion of guarantee/warranty period. However, Security Deposit may be converted to Performance Bank Guarantee.
- 5) Payment : 90% payment will be released on R/A bills against due certification and balance 10% will be released after 12 months from the date of completion of job. The retention money will be treated as Performance Guarantee
- 6) Validity : Offer should remain valid for a period of 90 days from the date of opening of this tender.
- 7) Quoted rate should remain firm till completion of the job and price variation shall not be entertained.
- 8) Price should be quoted both in figures and words and your quotation must be free from any kind of overwriting, alteration and correction.
- 9) BWT shall reserve the right to increase or decrease the ordered quantity at the same rate and terms.
- 10) BWT shall reserve the right to split up the tendered quantity.
- 11) BWT shall reserve the right to accept or reject the tender partly or fully without assigning any reason.
- 12) Liquidated Damages : In the event of failure to complete the job within the stipulated completion period, BWT reserves the right to recover a sum of 0.5% for every week or part thereof by way of LD subject to maximum limit of 5% of the ordered value.
- 13) Risk Purchase : In the event of failure on the part of the contractor to complete the job, BWT reserves the right to get the job done by other agency/agencies as per the purchase order and shall recover the extra cost thereof, if incurred, from contractor.

- 14) Arbitration : Any dispute or difference whatsoever, arising between the parties and the purchaser out of relating to the construction, meaning, scope, operation or effect of the contract or validity or the breach thereof shall be settled by arbitration in accordance with the Rules of Arbitration in pursuance thereof shall be binding on the contractor.
- 15) Guarantee : The job shall be guaranteed for a period of 12 months from the date of commissioning.
- 16) Delivery/Completion of job : The job shall be completed within 30 days from the date of receipt of purchase order.
- 17) Loading & Unloading of materials : Loading and unloading of materials from the transport during delivery of the materials will be the responsibility of the vendor.
- 18) Any legal dispute that may arises should be settle within the jurisdiction of Court of Kolkata.
- 19) Inspection: The entire job will be subject to inspection by BCL.
- 20) The tender is not transferable

**PART – II: PRICE BID**

- 1) The rate will remain firm till completion of supply.
- 2) The rate to be quoted both in figures and words.
- 3) Overwriting in price figure of the quotation will be rejected.
- 4) The bidder shall submit rate in the enclosed format.

For Braithwaite & Co. Ltd.,

Assistant Manager (Pur)

PRICE FORMAT

**A)ACCOUNTS DEPARTMENT:Strong Room & Cash Room Only**

SL. NO.	Description	Quantity	Unit Rate	Total Amt
1.	Dismantling,Re-sizing,Fitting & rigidly Fixing of 1no. 3'-6"x 6'-6" & 1 no. 3'-0"x7'-2" size(Total:44.25 sq.ft.)Steel Grill Door(Existing grill gate will be dismantled from A/cs deptt.)	2nos.		
2.	Dismantling,Fitting & Fixing of existing steel collapsible gate size:4'-0"x6'-6"(Total 26 sq.ft.) & shutter(Existing collapsible gate in place of D-6 Position by dismantling the same from existing A/cs room.	2nos.		
3.	Dismantling,Re-sizing,Fitting & Rigidly fixing of grill 2'-8"x13'-0" adjacent to the door D5(Sec B-B)& 7'-0" x7'-10" & 3'-6"x4'-0" Steel Grill –Door Portion D4(Sec A-A.=73.75sq.ft.)as per drawing.	2nos.		
4.	0'-5"(125mm)thk.Brickwork with cement Mortar(1:4) over floor & 12mm Cement Plaster(Cement sand mortar 1:6)with 10" neat cement finish on both sides of the wall including cost of material & labour.(~ 7.00 sq.m) a)4'-6" height x 13'-0" lg.~ 60sq.ft. b)3'-0" height x 5'-4" lg.~ 16sq.ft.	7m <sup>2</sup>		
5.	0'-10"(250mm)thk.Brickwork with cement Mortar(1:4) over floor & 19mm & 12mm Cement Plaster(Cement sand mortar-1:4)with 10" neat cement finish on both sides of the wall including cost of material & labour. a)10'-0" height x 6'-10" lg.~ 70sq.ft.-Vault room side. b)10'-0" height x 13'-0" lg.~ 130sq.ft.-Cash room side. c)10'-0" height x 7'-10" lg.~ 80sq.ft.-Corridor side. d)0'-10" height x 13'-0" lg.~ 11sq.ft.-Ceiling coverage. 3'-0" height x 21'-0" lg.~ 63sq.ft. " "	8.5m <sup>3</sup>		
6.	Transportation/shifting of vault /Iron safe from A/c dept. (2 <sup>nd</sup> Floor)to Gm's building 1 <sup>st</sup> Floor.	L.S.		
7.	Plaster Repairing(side wall & ceiling),White/colour wash (3coats)&painting(1 coat primer & 2 coats finish) of Iron beams,grills,grill gate,collapsible gate,rolling shutters wooden Frame,doors & windows after scrapping & cleaning etc.	30 m <sup>2</sup> 200 m <sup>2</sup> 47 m <sup>2</sup>		

**(B) PURCHASE DEPARTMENT:**

SL. NO.	Description	Quantity	Unit Rate	Total
1.	Supply & rigidly Fixing of 38mm thick 3'-6"x6'-6" Do or with 3"x3" size Sal Wood frame & panel with 1.5" thick Sal Wood frame covering both sides by 3mm thick Commercial ply wood (Best quality) with painting. (as per Drg.). Each door to be fitted with 1 No. Hyd. Door closure, 1 No. Mortise Lock (Godrej make) & other required accessories including cost of material & labour.	1 no.		
2.	Supply & Fixing of wooden board partition with 3"x3" Sal Frame, Covering by 1/8" thick Ply wood board (best quality) on both sides.  a) 3'-1" wide x 13'-0" lg. (Sec A-A) = 40 sq. ft. - M (Pur) Room. b) 3'-1" wide x 3'-5" lg. (Sec CC) = 10.5, Computer Room. c) 3'-1" wide x 12'-0" lg (sec CC) = 46 sq. ft. Computer Room. Including supply of 3"x3" Sal Wood Frame, Ply Wood, Labour Charge & etc to complete the work.			
3.	Fitting & fixing of 5mm thick clear glass in various sizes, Glass. (13 Nos.) will be fixed on paneling on Sal Wood frame by fixing in 3"x1.5" panel frame with aluminium section including supply of all materials & Al. Frame etc. to complete the job. a) 4'-0"x12'-6" - 50 sq. ft. - Front of M (Pur) b) 4'-0"x3'-0" - 12 sq. ft. - Front of Computer Room c) 4'-2"x12'-3"x2 - 102 sq. ft. - Partition			
4.	Construction of 5" thick brick work (Cement mortar 4:1) over floor level, Cement plaster with 10" neat cement finish including supply of all materials & labours.  a) 3'-0"x12'-6" lg (Sec A-A) = 37.5 sq. ft. - Front of M (Pur) b) 3'-0"x12'-3" lg x 2 (Sec BB & CC) = 73.5 sq. ft. partition c) 3'-0"x3'-0" lg (Sec AA) = 9 sq. ft.	3.42 m <sup>2</sup>		
5.	Construction of 10" thick brick wall (Cement mortar 4:1) over floor level Cement plaster with 10" neat cement finish including supply of all materials & labours.  a) 10"x10"x11'-10" = 8.2 Cu. ft. (Gap over ISMB)	0.2 m <sup>3</sup>		
6.	Plaster Repairing (side wall & ceiling), White/colour wash (3 coats) & painting of Iron beams, grills, grill gate, collapsible gate, rolling shutters, wooden frame, doors & windows (1 coat Primer & 2 coats finish) after proper scraping & cleaning etc.	10 m <sup>2</sup> 300 m <sup>2</sup> 47 m <sup>2</sup>		

**(C)P.P.C. & CAPITAL PROJECT DEPARTMENT:**

<b>SL. NO.</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit Rate</b>	<b>Total</b>
1.	Supply & rigidly of 3'-6"x6'-11".Size(2 Nos.)Door with 3"x3" size Sal Wood frame & panel (38mm thick) with 1.5"thk Sal Wood frame covering both sides by 3 mm thk.Commercial Ply wood (Best Quality)with pain -ting(as per Drg.).Each door to be fitted with 1no.Hyd. Door Closure,1no. Mortise Lock(Godrej Lock) & other required accessories to complete the job including supply of materials & labour.			
2.	Supply & Fixing of wooden board partition with 3"x3" Sal Frame,covering by 1/8"thk.Ply wood board(Best Quality) on both sides.  b)3'-1" wide x 32'-6" lg(Sec A-A)=100sq.ft. Including supply of 3"x3" Sal wood Frame,Ply wood, Labour charge & etc. to complete the work.	100Ft <sup>2</sup>		
3.	Construction of 5" thk brick work(Cement mortar 4:1) over floor level,both side cement plaster with 10" neat cement finish including supply of all materials & labour. 3'-0"x37'-4"(32'-6"- 7'-0"+11'-10")=112.0sq.ft.	7.1 m <sup>2</sup>		
4.	Fitting & Fixing of 5mm thick 'Clear Glass-17nos.'in various sizes.Glass to be fixed on paneling on Sal Wood frame 3"x3"& 3"x1.5" thk.Panel Frame with Aluminium section/frame including supply of all materials & Fasteners etc. to complete the job.(92.3sq.ft.)	92 Ft <sup>2</sup>		
5.	Plaster Repairing (side wall & ceiling),white/colour wash(3 coats) & painting(1 coat primer & 2 coats finish) of Iron beams,grills,grill gate,collapsible gate,rolling shutters,wooden Frame,doors & windows after proper scrapping & cleaning etc.	20 m <sup>2</sup> 200 m <sup>2</sup> 30 m <sup>2</sup>		
6.	Construction of 5"thk brick work(Cement mortar 4:1) over floor level,both side cement plaster with 10" neat cement finish including supply of all materials & labours d)3'-0"x50'-0"=150sq.ft. e)11'-0"x14'-0"=154sq.ft.	154 Ft <sup>2</sup>		
7.	1 no. Revolving Chair with castor wheel(make:Godrej)	1no.		

**(D) ENHANCEMENT OF COMPUTER ROOM FOR CONNECTIVITY CONSTRUCTION  
OF ONE NO. URINAL AT ANGUS WORKS(SIZE OF URINAL- 4'-6"X5'0"X8'-0"HIGH):**

SL. NO.	Description	Quantity	Unit Rate	Total
1.	10" Brickwork(6:1)excluding opening for door.	112 Ft <sup>2</sup>		
2.	4" RCC(1:2:4)Roof Casting 7'x 7'-6"	53 Ft <sup>2</sup>		
3.	¼"thick Cement plaster(7:1)inside the wall & Ceiling.	150 Ft <sup>2</sup>		
4.	½"thick Cement plaster(4:1)outside the wall.	200 Ft <sup>2</sup>		
5.	3'x6'6" Sintex Door shutter & door frame.	1no.		
6.	4'x3' wooden window fitted with glass pans	1no.		
7.	Godrej Morice Lock for Door	1no.		
8.	Fittings & Fixtures for door & window	L.S.		
9.	Glaze Tile(4"x4")upto 6' high	100 Ft <sup>2</sup>		
10.	Ceramic Urinal pot flat wall type(Parryware/Hindware)	1no.		
11.	Wash basin 18"x12"(Parryware/Hindware)	1no.		
12.	Necessary fittings and tap for urinal & basin	L.S.		
13.	Wall fitted Looking Glass 2'x1'6"	1no.		
14.	Soap stand, Towel Rod etc.	L.S.		
15.	Towel(Big & Small)- 3 + 3 pcs.	6nos.		
16.	½"galvenised Tata B-type pipe with required fittings	20m		
17.	4" PVC Pipe for draining out with fittings & fixtures	20m		

**(E)FURNITURE AND FITTINGS OF EXISTING ROOM:**

SL. NO.	Description	Quantity	Unit Rate	Total
1.	Revolving Sr.Executive Chair(Godrej make)	1no.		
2.	Front Chair(Godrej Make)	6nos.		
3.	Velvet and ¼" thick clear glass for existing Table	5nos.		
4.	Polishing of Existing Table	60 m <sup>2</sup>		
5.	Painting of existing Room & Toilet	50 m <sup>2</sup>		
6.	Electrical fittings for Room & Toilet	L.S.		

**(F) ENHANCEMENT OF COMPUTER ROOM CLEAN POWER FOR HEAD OFFICE, CLIVE WORKS & VICTORIA WORKS DUE TO CONNECTIVITY WITH ANGUS WORKS.**

<b>SL. NO.</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit rate</b>	<b>Total</b>
1.	Supply & fitting of False Ceiling with all fittings.	426 Ft <sup>2</sup>		
2.	Wooden door to new position and shifting of one existing door.	3nos.		
3.	Construction & fitting of wooden partition wall with fitting of two Air Conditioner.	315 Ft <sup>2</sup>		
4.	Enhancement Networking Infrastructure	1set (100 Ft)		
5.	Supply of Steel File cabinet(3 racks)-18"x27"x42"with Locking arrangement-Make Godrej/Steelux/Raj & Raj	2nos.		
6.	Supply of Wooden rack with sunmica top(3 racks)-3'x 1'-6"x3' high with locking arrangement	2nos.		
7.	Supply of wooden rack with sunmica top(3 racks)-4'x 2'x3' high with locking arrangement.	2nos.		
8.	Supply of sunmica table top(12'x4')to set on existing Table	1no.		
9.	Supply of sunmica table top(8'x4')to set on existing Table.	1no.		
10.	Supply of White table cloth for conference table(Table Size 12'x4')	2nos.		
11.	Supply of white table cloth for conference table(table Size 8'x4')	2nos.		
12.	Supply of computer chair fitted with custor wheel, Make Godrej/steelux	8nos.		
13.	Supply of computer table 5'x2'-6" including one Boar -d with 5 point electrical connection.	2nos.		
14.	Supply of computer table 4'x2' including one Board With 5 point electrical connection.	6nos.		
15.	Supply & fitting of Hydraulic door closer & Godrej Make Mortice Lock in existing door.	1 set		
16.	Supply of Front Grill for existing Air Conditioning Machines	4nos.		
17.	Supply of Brass name plate embossed with name of Departments (ERP,CPL &EDP)	3nos.		
18.	Supply and fitting of Calling bells with all accessories	3nos.		
19.	Supply of Curtains(Synthetic material)complete with All fittings and steel pipe.	1 set		
20.	Supply of wire less Audio system with 2 nos. button Microphone	1 set		
21.	Repairing of floor tiles (synthetic)with replacement of New tiles			
22.	Repairing/replacement of existing wall panel(laminated board)	100 Ft <sup>2</sup>		
23.	Re fixing of switch boards including new wiring where Applicable	L.S.		
24.	Refixing,Repairing/Replacement of existing Tube lights, sheds and fans	10 sets		
25.	Repairing of existing wall Almira h shutters to bring in Workable condition	L.S.		
26.	Repairing of existing Tables,table locks and chairs With replacements of chairs covers	25nos.		
27.	Painting/Polishing of walls and wooden/ply panels	70m <sup>2</sup> 50 m <sup>2</sup> 30 m <sup>2</sup>		
28.	Computer covers(Good Quality)	100nos.		

